EQUIPMENT PLAN GENERAL NOTES

1. REFER TO OWNER FURNISHED EQUIPMENT (OFE) MANUAL AND VENDOR DRAWINGS FOR EQUIPMENT IDENTIFICATION & REQUIREMENTS.

2. REFER MEP DRAWINGS FOR ALL DEVICES AND CONNECTIONS.

3. REFER TO A8 SERIES FOR CASEWORK NOTES & DIMENSIONS.

4. REFER TO A2 SERIES FOR TOILET ACCESSORY LEGEND AND TYPICAL MOUNTING HEIGHTS.

5. INSTALL TOILET ACCESSORIES TA-3 AND TA-9 (OWNER FURNISHED) AT ALL SINK AND LAVATORY LOCATIONS.

6. PROVIDE WALL BLOCKING AS REQUIRED FOR ALL WALL MOUNTED EQUIPMENT.

7. BOTTOM EDGE OF WALL MOUNTED TVs TO BE 80" A.F.F., MIN.

8. ALL WALL OUTLETS FOR POWER, CABLE, SATELLITE, ELECTRICAL, ECT TO BE INSTALLED FOR TELEVISION CONNECTIONS AT ALL TELEVISION LOCATIONS PER DRAWINGS NEED TO BE LOCATED TO BE DIRECTLY BEHIND THE TELEVISION AND NOT VISABLE FROM ANY ANGLE. COORDINATE WITH ELECTRICAL DRAWINGS.

9. ALL USB/POWER OUTLETS ABOVE COUNTERTOPS IN PHYSICIAN WORK STATIONS, NURSE STATIONS, NOURISHMENT AREAS, PHARMACY, MEDS, STAFF LOUNGES, RECEPTIONS, AND CONTROL AREAS TO BE MOUNTED HORIZONTALLY. REF ELECTRICAL DRAWINGS.

10. GC TO COORDINATE WITH OWNER INSTALLATION OF ALCOHOL BASED HAND RUBS (ABHRs). ABHRs SHALL NOT BE INSTALLED ABOVE OR DIRECTLY ADJACENT TO ALL ELECTRICAL DEVICES AND SWITCHES.

EQUIPMENT LEGEND

01/ A1.01 — CASEWORK ELEVATION

TA-XX — TOILET ACCESSORIES DEVICES, REF A2 SERIES AND SPECIFICATIONS FOR DETAILS

XXXX — INTERIOR FINISH PRODUCT, REF. FINISH SCHEDULE AND SPECIFICATIONS FOR DETAILS

XXXX — VENDOR EQUIPMENT TAG, REF. VENDOR DOCUMENTS AND EQUIPMENT MANUAL FOR DETAILS

1 EQUIPMENT PLAN
A8.00 SCALE: 1/8" = 1'-0"

ascension group ENVIRONMENTS FOR HEALTH ARCHITECTURE
e4h
888.781.9441 t 817.226.1917 1250 E. Copeland Rd. Suite 500, Arlington, TX 76011
BOSTON | DALLAS | NEW YORK | BURLINGTON | PORTLAND
e4harchitecture.com

©2016 Environments For Health

ISSUE FOR BID & PERMIT

NATIONAL CARDIOVASCULAR PARTNERS
NORTH HOUSTON CARDIOVASCULAR CENTER
19502 MCKAY DRIVE, SUITE 203 & 204, HUMBLE, TX 77338

No	Revision	Date

Project Number: 2016-109
Date: 11/18/2016
Sheet Title and Number:

A8.00
EQUIPMENT PLAN